

# Parkway Women's Medical Center

## Decatur, Alabama

*People, Building Excellence  
for People*



Type of Facility: Healthcare

#### Project Description:

- This project included the complete design and construction services for a 45,220 sq. ft. hospital addition including offices, labor and delivery functions, nursery, and C-Section rooms.
- Two built up air handlers with final filters were installed.
- Total cooling capacity of 80 tons was accomplished with air cooled condensing units.
- One 35 ton packaged unit serves the future third floor MOB.
- Critical areas are controlled through terminal boxes with hot water reheat coils and an electric humidifier.
- The building is controlled through a direct digital control system.
- The plumbing system included a complete medical gas system consisting of O<sub>2</sub>, vacuum, medical air, nitrogen, and nitrous Oxide.

General Contractor: Robins & Morton

Engineer: Lee Company

Total Contract: \$1,232,383.00

331 Mallory Station Road  
Franklin, TN 37067-8211

Phone: 615-567-1000

Fax: 615-567-1026

Email:

leecompany@leecompany.com

