

# Carmike Cineplex 20

## Franklin, Tennessee

*People, Building Excellence  
for People*



Type of Facility: Commercial

### Project Description:

- The scope involved the HVAC systems serving an approximately 150,000 sq.ft. facility with 20 screens, common area, concession area, and an equipment mezzanine.
- This facility is served by 55 DX package units with stand-alone controls. Unit sizes range from 4 tons to 15 tons.
- A helicopter was used to set all of the units in less than 2 hours. 200,000 pounds of sheet metal ductwork was installed, with the majority being fabricated in-house.
- Sound attenuators were provided on the ductwork supply and return serving the THX auditoriums with ductwork and air distribution installed to meet the stringent guidelines required for THX certification.

Owner: Carmike Theaters

Engineer: Campbell and Associates

Total Contract: \$1,259,780

331 Mallory Station Road  
Franklin, TN 37067-8211

Phone: 615-567-1000

Fax: 615-567-1026

Email:

leecompany@leecompany.com

